

Question 1: Whether the dismantling of the drum-separator is carried out in a containment building or it is dismantled by transferring it to a waste treatment facility after large-scale cutting.

The Drum-Separator and associated equipment dismantling, and fragmentation will be performed inside rooms 506/1,2. There are limitations on the dimensions of dismantled pieces of equipment associated with the dimensions of transportation opening, lifting mechanisms capacity and initial Waste Treatment Facility inside block A1. The limitations are following: Dismantled pieces of equipment must not exceed 1000 mm by 1000 mm and must not exceed lifting mechanism's capacity in the Drum-Separator rooms (rooms 506/1,2), as well as the lifting mechanisms' capacity in the initial Waste Treatment Facility. However, the Contractor is free to provide alternative dismantling strategy considering INPP's existing infrastructures and justify different limitations / restrictions.

Question 2: If a packaging container is provided.

The Contractor's scope of supply includes transportation of waste from Drum-Separator rooms to the initial Waste Treatment Facility, thereafter further waste operations will be conducted by the INPP personnel (including packaging).

The Contractor may propose an alternative way of transportation to the initial Waste Treatment Facility.

Question 3: If there are any restrictions on the cutting method. For example, whether a thermal method is not applicable, only a mechanical method is applicable.

There are no cutting method restrictions present. The cutting method will be selected and justified by the Contractor during the development of new or improvement of existing INPP Technological project. However, the selected cutting method must comply with Lithuanian H&S regulations and must be approvable by the state nuclear regulator, VATESI.

Question 4: Of all the series of devices and/or facility required to dismantle the drum-separator, which one can the client provide?

The full list of devices and/or facilities that client (INPP) will provide will be stated in the Technical Specification and in the Contract. Detail information cannot be provided at this time. However, sanitary checkpoints, personnel protective sets of equipment (PPE), ventilation of rooms, treatment, and disposal of secondary waste, potentially office space, etc. may be provided by the Client (INPP).

Question 5: Questions regarding the video materials shown during the workshop and the record of the workshop.

INPP has provided on its website links to the presentations provided during the Workshop on the 3rd March 2022 and these are available in the public domain. Some of the video materials shared during the Workshop are and remain the Intellectual Property of INPP and for various reasons, including Security, will not be distributed.